

MAIN FEATURES

- 1200 TONNES LIFTING CAPACITY ON FOUR LIFTING UNITS
- 300 TONNES LIFTING CAPACITY PER TELESCOPIC LIFTING UNIT
- HIGH HORIZONTAL LOAD CAPACITY
- ADJUSTABLE TRACK WIDTH FOR INCREASED STABILITY
- TRACKS CAN BE AT DIFFERENT LEVELS
- CENTRAL WIRELESS CONTROL OF ALL FUNCTIONS
- ACCURATE ADJUSTMENT OF THE LOAD POSITION TO +/-1mm IN ALL DIRECTIONS
- ALL COMPONENTS SUBJECT TO STATIC TEST AT 125% OF SWL AND DYNAMIC TESTS OF ALL FUNCTIONS AT 110% OF SWL IN ACCORDANCE WITH APPROPRIATE EUROPEAN DIRECTIVES
- COMPLETE DL-TLG1200 SYSTEM CE MARKED IN ACCORDANCE WITH APPROPRIATE EUROPEAN DIRECTIVES
- ALL COMPONENTS SUITABLE FOR TRANSPORT IN STANDARD SHIPPING CONTAINERS

DO NOT SCALE

This drawing has been produced by DLT Engineering in accordance with the instructions of the client for their sole and specific use.

DLT Engineering shall not be liable for the use of any information contained on this drawing for any purpose other than that for which it was specifically prepared and provided.

Should there be any doubt regarding the interpretation of any information given on this drawing, enquiries should be directed to DLT Engineering at the address given below before executing such part of the works.

Copyright © DLT Engineering Ltd.

NOTES

SPECIFICATION
DL-TLG1200, 4-POINT LIFT SYSTEM

- MAXIMUM SAFE WORKING LOAD (SWL) AT TOP OF TELESCOPIC CYLINDERS
STAGE 1 = 1200 TONNES @ 145 BAR WORKING PRESSURE
STAGE 2 = 780 TONNES @ 145 BAR WORKING PRESSURE
STAGE 3 = 472 TONNES @ 145 BAR WORKING PRESSURE
SEE DRAWINGS DL-TLG1200-005-01 AND 02 FOR LIFTING ARRANGEMENTS AND DUTY CHARTS
- STATIC TEST LOAD = 1.25 x SWL + MAXIMUM HORIZONTAL LOAD (TESTS CARRIED OUT AT FULL EXTENSION FOR EACH TELESCOPIC CYLINDER STAGE)
- DYNAMIC TEST LOAD = 1.10 x SWL (TESTS CARRIED OUT FOR EACH TELESCOPIC CYLINDER STAGE AND FOR ALL FUNCTIONS)
- MAXIMUM HORIZONTAL LOAD = 5% OF VERTICAL LOAD IN ANY DIRECTION (SEE OPERATION AND MAINTENANCE MANUAL FOR DETAILS).
- MAXIMUM SLOPE OF TRACK = 1% IN ANY DIRECTION (BOTH TRACKS AT SAME SLOPE WITHIN TOLERANCES SPECIFIED IN OPERATION AND MAINTENANCE MANUAL)
- MAXIMUM TRANSVERSE SLOPE OF HEAD BEAM = +/- 1%
- MAXIMUM WHEEL LOAD = 78 TONNES
- LIFTING AND LOWERING SPEED OF TELESCOPIC CYLINDER = 0.5 m/minute (FAST) AND 0.1 m/minute (SLOW) - CONSTANT FOR ALL TELESCOPIC CYLINDER STAGES
- LONGITUDINAL MOVEMENT SPEED OF DL-TLG1200 LIFTING UNITS = 3.0 m/minute (FAST) AND 1.0 m/minute (SLOW)
- TRANSVERSE MOVEMENT SPEED OF DL-TLG1200 POWERED TROLLEYS = 0.5 m/minute
- POWER SUPPLY = 380-420 VOLTS AT 50 Hz OR 440-480 VOLTS AT 60 Hz, 3 PHASE + EARTH
- MAXIMUM POWER CONSUMPTION = 30 kW RUNNING PER DL-TLG1200 LIFTING UNIT
- CONTROL FOR ALL FUNCTIONS = CENTRAL WIRELESS CONTROL CONSOLE OR CONTROL PANEL AT THE CENTRAL CONTROL UNIT OR LOCAL CONTROL PANEL AT EACH DL-TLG1200 LIFTING UNIT
- OPERATING TEMPERATURE = -20 TO +45 °C (SUBJECT TO HYDRAULIC OIL GRADE USED)
- ALL COMPONENTS OF DL-TLG1200 SYSTEM SUITABLE FOR TRANSPORT IN STANDARD SHIPPING CONTAINERS.

DL-TLG1200 HEAD BEAM TO SUIT TRACK CENTRES UP TO 11.2m SEE DRGS DL-TLG1200-003-01 & 02

2 No. DL-TLG1200 POWERED TROLLEYS PER HEAD BEAM WITH CHAIN DRIVE FOR SECURE LATERAL MOVEMENT. SAFE WORKING LOAD 300 TONNES PER UNIT SEE DRG DL-TLG1200-003-01

POWER AND CONTROL CABLES TO DL-TLG1200 LIFTING UNITS (BY DLT)

CENTRAL CONTROL UNIT (BY DLT) COMPRISING POWER DISTRIBUTION CABINET AND PLC CABINET

POWER IN (BY OTHERS) 120kW MAX RUNNING

DL-TLG1200 STANDARD TRACK SECTIONS AVAILABLE IN 2.8m AND 5.6m LENGTHS SEE DRG DL-TLG1200-004

WIRELESS CONTROL CONSOLE LINKED TO CENTRAL CONTROL UNIT

4 No. DL-TLG1200 LIFTING UNITS EACH WITH 3 STAGE TELESCOPIC CYLINDER. SAFE WORKING LOAD 300, 195 AND 118 TONNES PER UNIT FOR TELESCOPIC CYLINDER STAGES 1, 2 AND 3 SEE DRG DL-TLG1200-002

NOTE:
HEAD BEAMS WITH POWERED TROLLEYS SHOWN. HEAD BEAMS WITH STATIC HANGERS AVAILABLE. SEE DRG DL-TLG1200-003-02

DLT Engineering
International House
Midland Road, Higham Ferrers
Northamptonshire, NN10 8DN
United Kingdom
Tel: +44 (0) 1933 319133
www.dlteng.com

Project
DL-TLG1200
TELESCOPIC LIFTING GANTRY

Drawing Title
4 POINT TELESCOPIC LIFTING GANTRY
GENERAL ARRANGEMENT AND SPECIFICATION

Design Eng: JM	Checking Eng: PD
Drawn by: AW	Project Eng: SAB

Scales (At A3) AS SHOWN	Drawing Status INFORMATION
----------------------------	--------------------------------------

Original Drawing size: A3	Drawing No. DL-TLG1200-001	Rev. N1
---------------------------	--------------------------------------	-------------------